BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT31400

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/04/2018-19, Date: 24.08.2018

Providing Basic facilities for Ganesha Immersion at Ganesha temple kalyani Sahakaranagara in Kodigehalli ward no. 8.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of LIKITH V (SHREE BYRAVESHWARA CONSTRUCTIONS	
				In Figures	In Words
1	121	Supply of Drinking Water through water tankers of Capacity 6000 Liters and Hiring of Water Tanker Hiring of Tractor 40HP including cost of warer and Engaging Heavy Mazdoor to deliver water including cost of fuel lubricants men and machinary etc. complete	No	487.35	Rupees Four Hundred Eighty Seven and Thirty Five Paise Only
2	12.5	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 Code 400 metal Component	cum	760.0	Rupees Seven Hundred Sixty Only
3	66	Hire charge of pumping water 3.5 KL/hr capacity Pump	Hr	47.5	Rupees Forty Seven and Fifty Paise Only
4	176	Providing Causal Labours (Unskilled mazdoor Heavy)	Day	245.93	Rupees Two Hundred Forty Five and Ninety Three Paise Only
5	690	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis as per the engineer in charge.	M	61.75	Rupees Sixty One and Seventy Five Paise Only
6	17600	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 40ft = 1600 sqft)	Sft	7.6	Rupees Seven and Sixty Paise Only
7	165	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft)	Rft	16.15	Rupees Sixteen and Fifteen Paise Only
8	220	Hire Charge for Armless Plastic Chairs	No	3.8	Rupees Three and Eighty Paise Only
9	165	Hire Charge for Wooden Table of Size 6ft x 2ft	No	38.0	Rupees Thirty Eight Only
10	1320	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire (KPWD SR 2010-11 P.55/I.6 III b)	M	8.55	Rupees Eight and Fifty Five Paise Only
11	66	1321 Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges (PWD SR 2016-17 (P.XXXXVII / I.92)	Hr	598.5	Rupees Five Hundred Ninety Eight and Fifty Paise Only
12	99	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time	No	270.75	Rupees Two Hundred Seventy and Seventy Five Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92